

Type of Construction	Material	Test	Frequency of Acceptance Samples and Tests for Job Control	Construction Stages for Obtaining Sample or Test	Sample Size	Procedures		Remarks
						Sampling Method	Test Methods	
Special Protection for Rock Slopes Rock Bolting	Bolts (Slotted or Headed)	Accepted on certification	Accepted on certification	Before incorporation in work See ALDOT-195, Sec 2.3				Send certifications to Area Materials Engineer
	Wedges		Accepted on certification	Before incorporation in work See ALDOT-195, Sec 2.3				Send certifications to Area Materials Engineer
	Expansion Shells With Tapered Plug		Accepted on certification	Before incorporation in work See ALDOT-195, Sec 2.3				
	Roof Plates		Accepted on certification	Before incorporation in work See ALDOT-195, Sec 2.3				
Seam Sealing	Structural Concrete							
	Components		See Section 501					
	Cement							
	Coarse Aggregate		See Section 501					
	Fine Aggregate		See Section 501					
	Water		See Section 501					
	Concrete Additives		See Section 501					
Concrete	Test Cylinders		Min. one set of 2 28 day cylinders per project	During pour	AASHTO T-141	AASHTO T-141	AASHTO T-22	

Type of Construction	Material	Test	Frequency of Acceptance Samples and Tests for Job Control	Construction Stages for Obtaining Sample or Test	Sample Size	Procedures		Remarks
						Sampling Method	Test Methods	
	Pneumatic Concrete Blanket Components							
	Cement		See Section 501					
	Aggregates		See Section 501					
	Water		See Section 501					
	Additives		See Section 501					
	Wire Mesh		See Section 502					
	Bolts & Plate Washers	Accepted on certification		Before incorporation in work See ALDOT-195, Sec 2.3				Send certifications to Area Materials Engineer
Concrete	Test Cylinders	See ALDOT-231	During pour	ALDOT-231	ALDOT-231	ALDOT-231		
Asphalt Surfacing	Asphalt Cement	Physical	Certified Acceptance see ALDOT-243	See ALDOT-195 & ALDOT-243, sample from transporting vehicle if required by the Engineer	1 Gal. (4 L)	AASHTO T-40		Deliver to Central Lab. Use Sample Information Card Form BMT-1