Alabama Department of Transportation Bureau of Materials and Tests Testing Manual

Acceptance Sampling and Testing Schedule Section: 512

Revision: 5/18/10

			Frequency of			Procedures		
Type of Construction	Material	Test	Acceptance Samples and Tests for Job Control	Construction Stages for Obtaining Sample or Test	Sample Size	Sampling Method	Test Methods	Remarks
Precast Non-	Abutment	Physical	Pretested and	Before delivery to			Visual	See ALDOT-367
Prestressed	Caps, Bent		stenciled DOT	work site			inspection for	
Concrete Bridge	Caps, Span						damage or	
Members	Sections,		See ALDOT-367	See ALDOT-195			deformity	
	Curb Spans,							
	Abutment							
	Panels, Wing							
	Panels, Wing							
	Cap Panels							