

Concrete Median and Safety Barrier

Type of Construction	Material	Test	Frequency of Acceptance Samples and Tests for Job Control	Construction Stages for Obtaining Sample or Test	Sample Size	Procedures		Remarks
						Sampling Method	Test Methods	
Concrete Median and Safety Barrier	Precast Barriers	See Section 501	Pretested and stenciled ALDOT 350 TL 3 (See NCHRP Report 350) and technician number	Before delivery to work site. Before incorporation into work.	1 unit per Lot. See ALDOT 364 for Lot Size.	See ALDOT 364.	AASHTO T-22	See ALDOT-364 Report on BMT 72 and BMT 53.
	Concrete For Cast In Place Barriers	See Section 501						See ALDOT-170
	Steel Reinforcing	See Section 502						
	Backfill	See Section 214						