

ALABAMA DEPARTMENT OF TRANSPORTATION

General Application Special Provision

DATE: April 20, 2022

GASP No. 22-GA0015

EFFECTIVE DATE: August 1, 2022

SUBJECT: Moving and Covering Traffic Control Signs.

Alabama Standard Specifications, 2022 Edition, SECTION 740 shall be amended as follows:

SECTION 740 TRAFFIC CONTROL DEVICES FOR CONSTRUCTION WORK ZONES

740.03 Construction Requirements.

(a) Traffic Control Personnel, Devices, Equipment and Training.

Item 740.03(a)3 shall be replaced by the following:

3. Moving and Covering Traffic Control Signs and Other Devices While Not in Use.

During periods when signs and other devices are not being used for traffic control they shall be removed from the work area, covered with the specified material or otherwise positioned so they do not convey their message to the traveling public. If covered, the covering material shall be 1/2 inch {13 mm} (nominal size) exterior plywood or aluminum composite material cut to fit the shape of the sign panel. The covering material shall be installed in accordance with the plan details and in such manner that no damage will occur to the sign panel during installation. Covering material shall be maintained in a neat and workmanlike manner during its use.