Structure Excavation and Backfill for Drainage Structures, and Minor Structures

Acceptance Sampling and Testing Schedule Section: 214

Revision: 05/06/10

			Frequency of			Procedures		
Type of Construction	Material	Test	Acceptance Samples and Tests for Job Control	Construction Stages for Obtaining Sample or Test	Sample Size	Sampling Method	Test Methods	Remarks
Structure Excavation and Backfill for Drainage Structures, and Minor Structures	General Backfill	As required by the Engineer	As directed by the Engineer	Before delivery to work site				
	Special Materials for General Backfill							
	Commercial Aggregates	Sieve Analysis Unit Weight	Pretested See ALDOT-249	See ALDOT-195 & ALDOT-249	AASHTO T-27	AASHTO T-2	AASHTO T-27 ALDOT-253 AASHTO	Aggregate must be from an approved source. See Qualified Products List I-1 for approved sources
		Omit Weight			T-19		T-19	
	Local Material	Permeability	1 test per each 3000 yd ³ (2500 m ³) or fraction thereof in each proposed source	Pretested and approved before delivery to work site	25 lbs (12 kg)	ALDOT- 105	AASHTO T-215	Submit samples to Central Lab, use Information Card BMT- 1, Work Sheet Form BMT-30, Report Form BMT-5
		Sieve Analysis	Each 500 yd ³ (m ³) in each proposed source	Pretested and approved before delivery to work site	AASHTO T-27	ALDOT- 105	ALDOT-50	
	Foundation Backfill	As required by the Engineer	As directed by the Engineer	Before delivery to work site				