Treatment of Limesinks

Acceptance Sampling and Testing Schedule Section: 224

Revision: 05/06/10

			Frequency of			Procedures		
Type of Construction	Material	Test	Acceptance Samples and Tests for Job Control	Construction Stages for Obtaining Sample or Test	Sample Size	Sampling Method	Test Methods	Remarks
Treatment of Limesinks	Special Backfill Commercial Aggregate	Pretested	See ALDOT-249	See ALDOT-195				Must be from an approved source. ALDOT-249
	Seal Concrete Reinforce- ment Steel	See Section 503 See Section 502						