

Slurry Seal

Type of Construction	Material	Test	Frequency of Acceptance Samples and Tests for Job Control	Construction Stages for Obtaining Sample or Test	Sample Size	Procedures		Remarks
						Sampling Method	Test Methods	
Slurry Seal	Liquid Binder Material	Analysis	Same as Section as 401					
	Aggregate and Mineral Filler	Gradation	Same as Section 401					Contractor should submit samples of his proposed sources to the Central Laboratory at least two weeks before beginning operations for establishment of bitumen content
	Water	Chemical	Pretested by Central Laboratory. Sample each source proposed for use if a pond or stream. No test required for municipal systems	At least two weeks before beginning operations	4 qt. (4 L)	See Section 232		Ship to Central Laboratory for tests. Report on BMT-18
		Hardness	All Sources					
Mixture	Bitumen Content	Minimum one daily	During operations	4 qt. (4 L)	ALDOT-210	AASHTO T-110, ALDOT-319	Report on BMT-20	