Acceptance Sampling and Testing Schedule Section: 405 Revision: 08/10/2023

			Frequency of	Construction		Procedures		
m			Acceptance	Stages for		g		
Type of			Samples and Tests	Obtaining Sample		Sampling	Test	
Construction	Material	Test	for Job Control	or Test	Sample Size	Method	Methods	Remarks
Tack Coat	Liquid Bituminous Material or Emulsified Liquid Bituminous Material	Temperature Temperature	See ALDOT-243. For projects including 800 gallons or more sample tank once per material per job. For all projects sample the tank when plant has been idle for an extended period of time, or has used different paving grades of asphalt material, or has not received BMT-146 for shipments. See Construction	Before incorporation in work	1 qt (1 L) for Performance Graded Asphalt Binder (PGAB). 1 gal. (4 L) for emulsified asphalts	AASHTO T-40		Ship to Central Laboratory. Use metal cans for Liquid Binder. Use plastic containers for emulsified asphalts. Sample information card Form BMT-1. If contamination is suspected, sample as required by Engineer
		Correction	Manual for frequencies, methods, and reports					
		Application Rate						