## **Bridge Bearings**

Acceptance Sampling and Testing Schedule Section: 511 Revision: 7/8/2022

			Frequency of			Procedures		
			Acceptance	Construction Stages				
Type of			Samples and Tests	for Obtaining		Sampling	Test	
Construction	Material	Test	for Job Control	Sample or Test	Sample Size	Method	Methods	Remarks
Bridge Bearings	Elastomeric	Physical	ALDOT-195;	Before installation	Complete pad	ALDOT-	Visual for	See ALDOT-368 for
	Bearing Pads	and	Section 2.3 plus			210	workmanship	details
		Chemical	ALDOT-195;					
			Section 2.1.3 or					Must be from an
			ALDOT-195;					approved source. See list
			Section 2.2.2					I-17, Materials, Sources
			1 Pad per lot or see					and Devices With
			ALDOT-368					Special Acceptance
								Requirements.