

**Waterproofing and Dampproofing**

Type of Construction	Material	Test	Frequency of Acceptance Samples and Tests for Job Control	Construction Stages for Obtaining Sample or Test	Sample Size	Procedures		Remarks
						Sampling Method	Test Methods	
Waterproofing and Dampproofing	Liquid Binder Material	Physical	See ALDOT-243 If not pretested sample at project level	Before incorporation in work  See ALDOT-195	1 quart (1 L)	AASHTO T-40		Ship to Central Lab. Use Information Card Form BMT-1
	Asphalt Plank	Physical	Certified Tests	Before incorporation in work  See ALDOT-195		ALDOT-210	Check for damage and dimensions  AASHTO M-46	Ship to Central Lab. Use BMT-1
	Waterproofing and Dampproofing Fabric	Chemical and Physical	Pretested Certified Tests. If not sample at project level 1 sample per each 200 rolls or fraction thereof	Before incorporating in work  See ALDOT-195	1 yard (1 m) by full width of roll	ALDOT-210	Visual check for damage	Submit samples to Central Lab. Use Information Card BMT-1
	Mortar	See Section 611						