Steel Bridge Painting

Acceptance Sampling and Testing Schedule Section: 521 Revision: 6/1/10

			Frequency of			Procedures		
Type of Construction	Material	Test	Acceptance Samples and Tests for Job Control	Construction Stages for Obtaining Sample or Test	Sample Size	Sampling Method	Test Methods	Remarks
Steel Bridge Painting	Paints, Oils and Pigments	Physical	ALDOT-195; Section 2.4 plus one verification sample per project		1 gal. (L) each component			See Procedure and List III-1 in Materials, Sources, and Devices with Special Acceptance Requirements Manual