			Frequency of			Procedures		
Type of			Acceptance Samples and Tests	Construction Stages for Obtaining		Sampling	Test	
Construction	Material	Test	for Job Control	Sample or Test	Sample Size	Method	Methods	Remarks
Bridge Joint Seals	Preformed Elastomeric Compression Seals	See Section 450		-	•			
	Un- Reinforced Diaphragm Seal	Physical	ALDOT-195; Section 2.1.3 1 sample per lot	Prior to installing	3 ft. (1 m)	ALDOT- 210		Submit samples to Central Lab. Use Sample Information Card Form BMT-1
	Reinforced Diaphragm Seal	Physical	Certified Test Reports ALDOT- 195; Section 2.3	Prior to installing				