Storm Sewers

Acceptance Sampling and Testing Schedule Section: 533 Revision: 5/10/10

			Frequency of			Procedures		
Type of Construction	Material	Test	Acceptance Samples and Tests for Job Control	Construction Stages for Obtaining Sample or Test	Sample Size	Sampling Method	Test Methods	Remarks
Storm Sewers	Cast Iron Pipe, Ductile Iron Pipe, Vitrified Clay Pipe, ABS Composite Pipe, PVC Pipe Joint Sealers Bedding and Backfill	Chemical and Physical	Certified Test	Before incorporation in work See ALDOT-195				
	Concrete Pipe		Pretested ALDOT-364				Visual for damage	All pipe must be from an approved source
	Corrugated Metal Pipe	Chemical and Physical	Certified Test	Before incorporation in work See ALDOT-195			ALDOT 330	Submit BMT-60 with certifications to Division Materials Engineer