Brick and Concrete Block Masonry

Acceptance Sampling and Testing Schedule Section: 613 Revision: 5/12/10

			Frequency of			Procedures		
Type of Construction	Material	Test	Acceptance Samples and Tests for Job Control	Construction Stages for Obtaining Sample or Test	Sample Size	Sampling Method	Test Methods	Remarks
Brick and Concrete Block Masonry	Brick or Concrete Block	Physical	Minimum one (1) sample per source per project	Before incorporation in work See ALDOT-195	Brick— AASHTO T-32 Block Ten (10) blocks each lot each source	ASTM C-90 AASHTO T-32 and ALDOT- 210	See Section 805	Submit to Division Materials Engineer Use BMT-1
	Mortar	See Section 611						