Acceptance Sampling and Testing Schedule Section: 616 Revision: 6/21/10

|                         |                    |      | Frequency of                                       |  |             | Procedures         |                 |  |
|-------------------------|--------------------|------|--|--|-------------|--------------------|-----------------|--|
| Type of<br>Construction | Material           | Test | Acceptance<br>Samples and Tests<br>for Job Control | Construction Stages<br>for Obtaining<br>Sample or Test | Sample Size | Sampling<br>Method | Test<br>Methods | Remarks  |
| Soil Cement<br>Flume    | Cement             |      | Pretested from approved sources                    | Prior to use, see<br>ALDOT-195 and<br>ALDOT-227        |             |                    |                 | Must be from an approved source. See List I-2, Materials, Sources and Devices with Special Acceptance Requirements. Report on BMT-1. |
|                         | Water              |      | Approved prior to use                              | Prior to use   |             | See Section<br>807 |                 | No testing required for potable water sources.   |
|                         | Aggregate          |      |  | Before incorporation in work                           |             |                    |                 | See Section 826  |
|                         | Joint<br>Filler    |      |  |  |             |                    |                 | See Section 832  |
|                         | Solid Sod          |      |  |  |             |                    |                 | See Section 654  |
|                         | Curing<br>Compound |      | Approved prior to use                              | Prior to use   |             | AASHTO<br>M-148    | AASHTO<br>M-148 | Must be from an approved source. See List II-30, Materials, Sources and Devices with Special Acceptance Requirements.                |