Headlight Glare Screen

Acceptance Sampling and Testing Schedule Section: 632

Revision: 6/17/10

			Frequency of			Procedures		
Type of Construction	Material	Test	Acceptance Samples and Tests for Job Control	Construction Stages for Obtaining Sample or Test	Sample Size	Sampling Method	Test Methods	Remarks
Headlight Glare Screen	Glare Screen	Physical	Certified Tests See ALDOT-195; Section 2.3	Before delivery to work site	•		Visual for damages	
	New Post	Physical	Certified Test ASTM A-36 Galvanized ASTM A-123					
			Guardrail post					See List II-17, Materials, Sources, and Devices With Special Acceptance Requirements Manual