Acceptance Sampling and Testing Schedule Section: 650 Revision: 04/14/09

			Frequency of			Procedures		
Type of Construction	Material	Test	Acceptance Samples and Tests for Job Control	Construction Stages for Obtaining Sample or Test	Sample Size	Sampling Method	Test Methods	Remarks
Topsoil	Topsoil	Topsoil Analysis	Minimum one (1) test each 5000 cy	Sampling to be done during initial drilling for design. Offsite material shall be tested at the rate of one test each 5000 cy. After stockpiling, additional testing required at the rate of one test each 5000 cy for onsite or offsite	15 pounds	ALDOT 105	ALDOT Section 650	Report in Site Manager
				material.				