## **Delineators and Hazard Markers**

Acceptance Sampling and Testing Schedule Section: 707 Revision: 5/13/10

			Frequency of			Procedures		
Type of Construction	Material	Test	Acceptance Samples and Tests for Job Control	Construction Stages for Obtaining Sample or Test	Sample Size	Sampling Method	Test Methods	Remarks
Delineators and Hazard Markers	Single Reflectors and Multiple Reflector Units Aluminum Backup Plates	Physical	ALDOT-195; Section 2.4	Prior to use			Visual for damage and dimensions	See List V-2, Materials, Sources, and Devices With Special Acceptance Requirements Manual
	Standard or Special Sign Panels Steel and Flexible Posts Concrete for	Chemical Physical	ALDOT-195; Section 2.3 or Section 2.1.3	Prior to use	See ALDOT-245		Visual for damage and dimensions	No test cylinders
	Posts		200 20000000					required