Alabama Department of Transportation Bureau of Materials and Tests Testing Manual

## Overhead Sign Structures Renovation or Relocation

Acceptance Sampling and Testing Schedule Section: 717 Revision: 5/13/10

			Frequency of			Procedures		
Type of			Acceptance Samples and Tests	Construction Stages for Obtaining		Sampling	Test	
Construction	Material	Test	for Job Control	Sample or Test	Sample Size	Method	Methods	Remarks
Overhead Sign	Any New	Chemical	ALDOT-195;	Prior to installation	See Remarks			Sample materials at
Structures	Materials	Physical	Section 2.3 or					frequencies set for new
Renovation or			Section 2.1.3					structures in Section 715
Relocation								