Alabama Department of Transportation Bureau of Materials and Tests Testing Manual

			Guide Frequency		Procedures			
Type of Construction	Material	Test	for Independent Assurance Samples and Tests	Construction Stages for Obtaining Sample or Test	Sample Size	Sampling Method	Test Methods	Remarks
Concrete Retaining Walls Note: This	Selected Backfill (Local Materials)	Gradation Atterberg Limits	One (1) per 7500 yd ³ (6000 m ³) or less	Same point in the process as the Acceptance Test	See AASHTO T-2, Table No. 1	ALDOT-210 AASHTO T-2	AASHTO T-27 AASHTO T-89 as	IAS&T-D Item See Special Provision or plans for gradation
Section is by Job Specific Special Provision							modified by ALDOT-232 AASHTO T-90 AASHTO M-145	requirements. Make comparison in accordance with ALDOT-341
	(Commercial Aggregate)	Gradation	See Section 401					IAS&T-D Item